

AD-A105 547

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE
NATIONAL DAM SAFETY PROGRAM. HAMILTON CITY WATER PLANT DAM (MO --ETC(U)
JUL 80 R S DECKER, G JAMISON, G ULMER


F/G 13/13

DACW43-80-C-0071

NL

UNCLASSIFIED

1 of 1
AD 3
10/1/87



END
DATE
FILMED
11-81
DTIC

AD A105547

LEVEL *14*

0
PS

GRAND-CHARITON BASIN

HAMILTON CITY WATER PLANT DAM

CALDWELL COUNTY, MISSOURI

MO. 10261

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM



United States Army
Corps of Engineers

... Serving the Army
... Serving the Nation

St. Louis District

DTIC
ELECTR
OCT 15 1981
A

DTIC FILE COPY

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

JULY, 1980

This document has been approved
for public release and sale; its
distribution is unlimited.

81 10 15

V
BS

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. <i>AD-A105547</i>	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Hamilton City Water Plant Dam (MO 10261) Caldwell County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Hoskins-Western-Sonderegger, Inc. <i>Rey S. /Decker Gordon /Jamison Garold /Ulmer Harold P./Hoskins</i>		6. PERFORMING ORG. REPORT NUMBER
9. PERFO U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) <i>DACW43-80-C-0071</i>
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS <i>11 12 13 14 15</i>
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) National Dam Safety Program. Hamilton City Water Plant Dam (MO 10261), Grand - Chariton Basin, Caldwell County, Missouri. Phase I Inspection Report.		12. REPORT DATE July 1980
16. DISTRIB Approved for release; distribution unlimited.		13. NUMBER OF PAGES Approximately 75
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
18. SUPPLEMENTARY NOTES		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

HAMILTON CITY WATER PLANT DAM
CALDWELL COUNTY, MISSOURI
MISSOURI INVENTORY NO. MO 10261

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY
HOSKINS-WESTERN-SONDEREGGER, INC.
CONSULTING ENGINEERS
LINCOLN, NEBRASKA

UNDER DIRECTION OF
ST. LOUIS DISTRICT, CORPS OF ENGINEERS

FOR
GOVERNOR OF MISSOURI

JULY, 1980

Accession For
NTIS GRA&I
DTIC TAB
Unannounced
Justification
By

A



REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 TUCKER BOULEVARD, NORTH
ST. LOUIS, MISSOURI 63101

SUBJECT: Hamilton City Water Plant Dam Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Hamilton City Water Plant Dam (MO 10261).

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, non-emergency by the St. Louis District as a result of the application of the following criteria:

- a. Spillway(s) will not pass 50 percent of the Probable Maximum Flood without overtopping the dam.
- b. Overtopping of the dam could result in failure of the dam.
- c. Dam failure significantly increases the hazard to loss of life downstream.

SUBMITTED BY:

SIGNED

Chief, Engineering Division

5 JAN 1981

Date

APPROVED BY:

Colonel, CE, District Engineer

SIGNED

5 JAN 1981

Date

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
	SECTION 1 - PROJECT INFORMATION	
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	3
	SECTION 2 - ENGINEERING DATA	
2.1	Design	7
2.2	Construction	7
2.3	Operation	7
2.4	Evaluation	7
	SECTION 3 - VISUAL INSPECTION	
3.1	Findings	8
3.2	Evaluation	10
	SECTION 4 - OPERATIONAL PROCEDURES	
4.1	Procedures	12
4.2	Maintenance of Dam	12
4.3	Maintenance of Operating Facilities	12
4.4	Description of Any Warning System in Effect	12
4.5	Evaluation	12
	SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1	Evaluation of Features	13
	SECTION 6 - STRUCTURAL STABILITY	
6.1	Evaluation of Structural Stability	15
	SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1	Dam Assessment	16
7.2	Remedial Measures	16

APPENDIX A - MAPS

Plate A-1
Plate A-2

Vicinity Topography
Location Map

APPENDIX B - PHOTOGRAPHS

Plate	Photo No.	Photo Index
Plate B-1	2	Overview Taken From Upper Left Side
Plate B-2	3	Entrance Channel To Principal Spillway. Looking Downstream To Concrete Chute.
Plate B-3	4	View Of Principal Spillway Chute Taken From Left Side
	5	Looking Down Principal Spillway Chute From Left Side
Plate B-4	6	View Of Opening Of First Joint On Left Side Of Principal Spillway Chute
	7	View Of Forebay Of Principal Spillway Chute Taken From Left Side
Plate B-5	8	Downstream View Of Principal Spillway Chute
	9	Concrete Scaling At Second Joint On Left Side Of Principal Spillway Chute
Plate B-6	10	Misalignment Of Downstream Section Of Spillway On Left Side
	11	Misalignment of Downstream Section Of Spill- way On Right Side
Plate B-7	12	Concrete Scaling Upstream Of Chute Blocks On Left Side Of Centerline
	13	Concrete Scaling Upstream Of Chute Blocks On Right Side Of Centerline
Plate B-8	14	Upstream Face Taken From End Of Left Leg Of Dam
	15	Crest And Downstream Slope On Left Leg Of Dam
Plate B-9	16	Upstream Slope Of Main Dam Taken From Left Leg of Dam
	17	Crest Of Main Dam Taken From Left At Point Of Curvature With Left Leg
Plate B-10	18	Downstream Slope Of Main Dam Taken From Left
	19	Upstream Slope Of Left End Of Main Dam Show- ing Erosion And Deterioration Of Riprap
Plate B-11	20	View Upstream With Intake Tower To Water Treatment Plant In Foreground
	21	View Downstream Taken From Intake Tower Loca- tion. Bridge At Extreme Left Spans Outlet Channel
Plate B-12	22	Downstream Slope Taken From Right
	23	Crest Of Main Dam Taken From Right. Man In Background Standing In Sag Over Or Near Pipe From Intake Tower To Water Treatment Plant

Plate B-13	Photo No. 24	Vertical Drop And Erosion Of Upstream Face Near Right End
	Photo No. 25	View Upstream In Emergency Spillway. Dike And Road Crossing Spillway Shows In Cen- ter Of Picture
Plate B-14	Photo No. 26	View Downstream In Emergency Spillway
	Photo No. 27	View Of Upstream Face Taken From Right End
Plate B-15	Photo No. 28	View Of Principal Spillway Chute And Down- stream Channel Taken From Highway Bridge
	Photo No. 29	House In Floodplain, 2 Miles Downstream Of Dam

APPENDIX C - PROJECT PLATES

Plates C-1 through C-5	Construction Plans - Kenneth H. Larkin and Associates
Plate C-1	Map Of Lake
Plate C-2	Layout Of Dam Site
Plate C-3	Dam Details
Plate C-4	Details Around Filtration Plant
Plate C-5	Spillway Details
Plate C-6	Phase I - Plan And Centerline Profile Of Dam
Plate C-7	Phase I - Cross Section Of Dam - Sta. 10+30+

APPENDIX D - HYDRAULIC AND HYDROLOGIC COMPUTATIONS

Plates D-1 and D-2	Hydrologic Computations
Plate D-3	Outflow Rating Curves
Plate D-4	Elevation - Area Curve
Plate D-5	Ratio-Discharge Curve
Plate D-6 through D-28	Computer Input and Output for Ratios of PMF

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM
ASSESSMENT SUMMARY

Name of Dam	Hamilton City Water Plant Dam
State Located	Missouri
County Located	Caldwell County
Stream	Tom Creek
Date of Inspection	July 1, 1980

Hamilton City Water Plant Dam was inspected by an interdisciplinary team of engineers from Hoskins-Western-Sonderegger, Inc. The purpose of the inspection was to make an assessment of the general conditions of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.

The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers and developed with the help of several Federal and State agencies, professional engineering organizations, and private engineers.

Hamilton City Water Plant Dam has a height of thirty-six (36) feet and a storage capacity at the minimum top elevation of the dam of twelve hundred (1200) acre-feet. In accordance with the guidelines, an intermediate size dam has a height greater than or equal to forty (40) feet but less than one hundred (100) feet and a storage capacity greater than or equal to one thousand (1,000) acre-feet but less than fifty thousand (50,000) acre-feet. The size classification is determined by either the storage capacity or height, whichever gives the larger size category. Hamilton City Water Plant Dam is classified as an intermediate size dam.

In accordance with the guidelines and based on visual observation, the dam is classified as having a high potential for damage and loss of life. Failure would threaten life and property. The estimated damage zone extends approximately seven (7) miles downstream of the dam. Within the damage zone are the City of Hamilton water treatment plant and Highway 36 Business Route (immediately downstream), Highway 36 (0.3 miles downstream), two dwellings and two barns (2.3 miles downstream), one dwelling and two barns (2.8 miles downstream) and Highway 13 (3.3 miles downstream).

Our inspection and evaluation indicate that the spillways do not meet the minimum criteria set forth in the recommended guidelines for an intermediate dam having a high hazard potential. The Probable Maximum Flood is the appropriate spillway flood. The spillways will pass the 100-year flood (a flood having a 1 percent probability of being exceeded in any year) without overtopping the dam. The spillways will pass 30 percent of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected

from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

Construction plans were available for this dam. Based on the information available from the plans and the observations made during the field inspection, the following deficiencies were found: inadequate spillway capacity, lack of seepage and stability analyses, tree growth on embankment and in outlet channel of the concrete spillway, erosion of areas of the upstream slope, displacement of the downstream sections of the concrete stilling basin, and open joints and scaling concrete in the concrete spillway. Remedial measures and maintenance procedures are recommended as listed below. All remedial measures should be performed under the guidance of a professional engineer experienced in the design and construction of dams.


a. Alternatives

- (1) The spillway size and/or the height of dam should be increased to pass the Probable Maximum Flood without overtopping the dam.

b. Operation and Maintenance Procedures

- (1) Seepage and stability analyses comparable to the requirements of the recommended guidelines should be performed by a professional engineer experienced in the design and construction of dams.
- (2) Trees should be removed from the embankment slopes and the outlet channel of the concrete spillway. This should be done under the guidance of a professional engineer experienced in the design and construction of dams.
- (3) The eroded areas of the upstream slope should be repaired and additional riprap provided in order to prevent further erosion and deterioration of the slope. This should be done under the guidance of a professional engineer experienced in the design and construction of dams.
- (4) The last downstream sections of the concrete stilling basin should be monitored periodically to determine whether the inward displacement at the top of the walls is increasing. Remedial measures may be required.
- (5) The joints on the concrete spillway structure should be checked for missing joint filler. Open joints should be resealed.
- (6) The areas of the floor section and the walls of the concrete spillway structure where scaling has occurred should be repaired.

- (7) The present practice of mowing the embankment is excellent and should be continued.
- (8) A program of periodic inspection and maintenance should be initiated. Records of inspections should be made a part of the project file.




Rey S. Decker
E-3703



Gordon Jamison



Garold Ulmer
E-19246



Harold P. Hoskins, Chairman of the Board
Hoskins-Western-Sonderegger, Inc.
E-8696



PHOTO NO. 1 - OVERVIEW

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
HAMILTON CITY WATER PLANT DAM - MO 10261
CALDWELL COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army through the Corps of Engineers to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District Corps of Engineers District Engineer directed that a safety inspection of Hamilton City Water Plant Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams," dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances.

- (1) The dam is an earth fill of intermediate size located in the dissected till plains area within the Central Lowlands Physiographic Region about a mile west of Hamilton, Missouri. The dam is approximately 1300 feet in length with a maximum height of about 36 feet. The maximum water storage at the minimum top elevation of the dam is 1200 acre-feet.

The dam consists of two legs with the principal embankment oriented almost east-west and the secondary wing dike oriented northeast-southwest. The principal or primary spillway is located at the left end of the secondary wing dike. There is an emergency or secondary spillway cut through the right abutment of the principal (east-west) embankment.

- (2) The principal spillway is uncontrolled and consists of a vegetated earth approach channel excavated in the left abutment leading to a St. Anthony Falls type reinforced concrete chute.
 - (3) An uncontrolled, vegetated earth emergency spillway is cut through the right abutment. A 4-foot high dike used for a road crossing is constructed normal to the spillway along the centerline of the dam.
 - (4) Pertinent physical data are given in paragraph 1.3 below.
- b. Location. The dam is located in the north central portion of Caldwell County, Missouri, about 1 mile west of the City of Hamilton as shown on Plate A-2. The dam is shown on Plate A-1 in the SW1/4 of Section 15, T57N, R28W.
 - c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Hamilton City Water Plant Dam has a height of 36 feet and a storage capacity of 1,200 acre-feet. This dam is classified as an intermediate size dam. An intermediate size dam has a height greater than or equal to 40 feet but less than 100 feet and a storage capacity greater than or equal to 1,000 acre-feet but less than 50,000 acre-feet. The size classification is determined by either the storage or height, whichever gives the larger size capacity.
 - d. Hazard Classification. Guidelines for determining hazard classification are presented in the same guidelines as referenced in paragraph 1.1c above. Based on referenced guidelines this dam is in the High Hazard Potential Classification. The estimated damage zone extends approximately seven miles downstream of the dam. It was determined by visual observation that within the damage zone are the City of Hamilton water treatment plant and Highway 36 Business Route (immediately downstream), Highway 36 (0.3 miles downstream), two dwellings and two barns (2.3 miles downstream), one dwelling and two barns (2.8 miles downstream), and Highway 13 (3.3 miles downstream).
 - e. Ownership. The dam is owned by the City of Hamilton, City Hall, Hamilton, Missouri 64644.
 - f. Purpose of Dam. The dam was constructed primarily as a source of water supply for the City of Hamilton, Missouri. It also provides recreation for the residents of the surrounding area.
 - g. Design and Construction History. Mr. Kuhnert, Water Superintendent for the City of Hamilton, stated that the initial dam construction at this site was done in 1920. The original dam was constructed with a 6-inch concrete core wall. In 1954 the dam as it presently exists was constructed from plans prepared by Kenneth H. Larkin

and Associates, Consulting Engineers, Kansas City, Missouri. The concrete core wall was left in place; the height of the dam was raised 12 feet +; the left wing of the dam was constructed; the dam was extended approximately 365 feet on the right and the two spillways were constructed.

- h. Normal Operating Procedure. The intake tower for the city water supply is equipped with two 8-inch cast iron intake pipes which are controlled by hand-operated rising stem gate valves. Water is drawn from the intake tower into the filtration plant through one 8-inch cast iron pipe as required to meet the City's demand for water. The pool level behind the dam is controlled by rainfall, infiltration, evaporation, the capacity of the uncontrolled spillways and the demand for potable water by the City of Hamilton.

1.3 PERTINENT DATA

- a. Drainage Area. 1,141 acres (1.783 square miles).
- b. Discharge at Damsite.

(1) Discharges at the damsite are through the following:

- (a) An uncontrolled principal spillway consisting of a vegetated earth approach channel excavated in the left abutment leading to a St. Anthony Falls type reinforced concrete chute having a crest width of 110 feet.
- (b) An uncontrolled vegetated earth emergency spillway, 85 feet in width, excavated in the right abutment. A 4-foot high dike crosses the spillway normal to the centerline of the spillway.
- (c) An intake tower equipped with two 8-inch cast iron intake pipes which are manually controlled by rising stem gate valves. Water is drawn from the intake tower through an 8-inch cast iron pipe into the Hamilton water treatment plant located at the downstream toe of the dam.

- (2) Estimated Maximum Flood at Damsite. The City Water Superintendent, Mr. Kuhnert, stated that 18 to 24 inches of water flowed through the control section of the principal spillway in 1964 or 1965.
- (3) The principal spillway capacity varies from 0 c.f.s. at elevation 110.0 feet to 2050 c.f.s. at the crest of the emergency spillway (elevation 113.5 feet) to 2250 c.f.s. at the minimum top of dam (elevation 113.7 feet).
- (4) The emergency spillway capacity varies from 0 c.f.s. at its crest elevation 113.5 feet to 7 c.f.s. at elevation 113.7 feet (minimum top of dam).

- (5) Total spillway capacity at the minimum top of dam is
2257 c.f.s. \pm

c. Elevations. (Local datum to conform with construction plans)

- (1) Observed pool - 108.7
- (2) Normal pool - 110.0
- (3) Spillway crest(s)
 - Principal - 110.0
 - Emergency - 113.5
- (4) Maximum experienced pool - 112 \pm
- (5) Top of dam (minimum) - 113.7
- (6) Streambed at centerline - 78 \pm
- (7) Maximum tailwater - unknown

d. Reservoir - Length (feet) of Pool.

- (1) At principal spillway crest - 4,000 \pm
- (2) At emergency spillway crest - 4,300 \pm
- (3) At top of dam (minimum) - 4,300 \pm

e. Storage (Acre-feet).

- (1) Observed pool - 800 \pm
- (2) Normal pool - 900 \pm
- (3) Spillway crest(s)
 - Principal - 900 \pm
 - Emergency - 1200 \pm
- (4) Maximum experienced pool - 1050 \pm
- (5) Top of dam (minimum) - 1200 \pm

f. Reservoir Surface (Acres).

- (1) Observed pool - 67 \pm
- (2) Normal pool - 73 \pm
- (3) Spillway crest(s)
 - Principal - 73 \pm
 - Emergency - 90 \pm
- (4) Maximum experienced pool - 82 \pm
- (5) Top of dam (minimum) - 91 \pm

g. Dam.

- (1) Type - Homogeneous rolled earth fill
- (2) Length - 1300 feet \pm
- (3) Height - 36 feet \pm (maximum)
- (4) Top width - 10 feet \pm (plans); 13 feet (measured)
- (5) Side slopes -
 - (a) Downstream - 1V on 3H (Plans and measured). 1V on 2.25H (Plans and measured above filter building)
 - (b) Upstream - 1V on 2H (Plans) 1V on 2.75H (measured on exposed face)

- (6) Zoning - none
- (7) Impervious core - 6" concrete core wall - Sta. 6 + 65 to Sta. 12 + 50.4 in old dam which forms an upstream berm for the existing dam.
- (8) Cutoff - unknown
- (9) Grout curtain - none
- (10) Wave protection - Riprap (8-10 inch maximum size)
- (11) Drains - Pervious blanket (Sta. 8 + 50 to Sta. 11 + 50) with 6-inch perforated corrugated metal pipe connecting to manhole at water treatment plant. The location of the pervious blanket is shown on Plate C-2.
- h. Diversion Channel and Regulating Tunnel - none
- i. Spillway.
 - (1) Principal
 - (a) Type - An uncontrolled vegetated earth approach channel excavated in the left abutment leading to a St. Anthony Falls type reinforced concrete chute having a crest width of 110 feet and a total length from crest to end sill of 180 feet.
 - (b) Crest Elevation - 110.0
End Sill Elevation - 79.0
 - (c) Upstream Channel - Free of obstructions and well vegetated.
 - (d) Downstream Channel - Well vegetated, few trees, highway bridge about 450 feet downstream from spillway chute.
 - (2) Emergency
 - (a) Type - Uncontrolled vegetated earth spillway having a width of 85 feet and side slopes of 1V on 4H.
 - (b) Control Section - A 4-foot high dike crossing the spillway normal to the spillway centerline.
 - (c) Crest Elevation - 113.5
 - (d) Upstream Channel - Well vegetated, open
 - (e) Downstream Channel - Well vegetated, open

- j. Regulating Outlets - Water is supplied to the city water intake tower by either of two 8-inch cast iron pipe intake lines that extend from the intake tower into the reservoir. These lines are manually controlled by operation of rising stem gate valves mounted within the intake tower on the ends of the intake pipes. Water is drawn from the intake tower into the filtration plant through an 8-inch cast iron pipe which is gate valve controlled within the filtration plant. The lower intake line from the reservoir has one cut-off collar. The 8-inch outlet pipe from the intake tower to the filtration plant is equipped with two cut-off collars. Details are shown on Plate C-4.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

No design data were available for the original dam which was constructed in the 1920's. The plans prepared in 1953 by Kenneth H. Larkin and Associates, Consulting Engineers, Kansas City, Missouri for the enlargement of the dam show the original dam and its spillway as they were prior to the construction in 1954. The plans for the 1954 construction are included in Appendix C.

2.2 CONSTRUCTION

The surveys and measurements made during the inspection indicate that the dam and its spillways were constructed in 1954 in accordance with the plans included in Appendix C. The 6-inch concrete core wall, which was a feature of the original dam, was left in place and the new embankment was constructed on the downstream side of the core wall. The spillway of the original dam was removed, and the dam was extended by construction of the left wing. The dam was also extended approximately 365 feet on the right side. An earth spillway was constructed through the right abutment, and an earth channel leading to a St. Anthony Falls type reinforced concrete spillway chute was constructed through the left abutment.

2.3 OPERATION

No data were available on spillway operation. It was reported by Mr. Kuhnert that the maximum flow through the spillway was about 18 to 24 inches deep which occurred sometime in 1964 or 1965. There has been no significant flow through the spillway since 1974. There was no evidence that would indicate that the dam has been overtopped.

2.4 EVALUATION

- a. Availability. The data included in Appendix C were readily available from the City of Hamilton.
- b. Adequacy. The available data, field surveys and visual observation presented herein are considered adequate to support the conclusions of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. The available data and information supplied by Mr. Kuhnert are considered valid and acceptable.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

- a. General. A visual inspection of the Hamilton City Water Plant Dam was made on July 1, 1980. Engineers from Hoskins-Western-Sonderegger, Inc., Lincoln, Nebraska, making the inspection were: Rey S. Decker, Geotechnical; Gordon Jamison and Garold Ulmer, Hydrology and Hydraulics. Mr. B. Kuhnert, Water Superintendent, accompanied the inspection team for part of the time.

b. Dam.

- (1) Geology and Soils (abutment and embankment). The Hamilton City Water Plant Dam is located in the dissected till plains area within the Central Lowlands Physiographic Region. The dam is in a region where the stratigraphic sequence consists of 8 to 16 feet of loess overlying Kansan-age glacial till, of undeterminable thickness and character, which in turn overlies bedrock of the Kansas City Group, Missourian Series, Pennsylvanian System. Strata of this group consists of interlayered shales, limestones, sandstones, and thin beds of coal.

The upland soil deposits in the dam area consist of the Adair-Lagonda-Shelby soil association. These soils are formed from loess which overlies glacial till and formed on a rolling to gently rolling topography. The Adair soil has formed in the uppermost and weathered portion of the glacial till. The Lagonda soil has formed from loess occupying positions on gently rolling uplands and interstream divides. The Shelby soil occupies the steeper slopes and has developed from relatively unweathered glacial till.

Materials observed in the abutments consist of CL loess-till colluvium. No till nor bedrock was observed at the site. Materials in the embankment consist of silty clay (CL) soils apparently taken from the spillway excavations and from the upstream abutment areas.

- (2) Upstream Slope. The upstream slope is fairly well plated with limestone riprap. The riprap is quite small with nominal size of 1 to 1.5 inches and maximum size of 8 to 10 inches. Some deterioration of the riprap was noted. Some erosion of the slope, 2 to 3 feet above the lake level, was noted along most of the main (E-W) dam. In some areas a near

vertical scarp has developed. In the area between about station 9+00 to 11+00 (stationing according to plans), concrete rubble has been added to the original riprap. A few small trees are growing on the upstream slope. No slumps, slides or abnormal deformations were noted on the slope. Photos No. 14, 16, 19, 24 and 27 show the upstream slope.

- (3) Crest. The crest is well vegetated with adapted grasses and legumes. No cracks were observed on the crest. The survey of the crest of the dam indicates that the embankment has settled more than anticipated through the area of the old channel. A note on Plate C-3 of the construction plans specifies overfill between stations 3+00 and 16+00 to allow for settlement. The sag in the crest begins at station 7+00 and ends at station 13+00. The lowest point in the crest occurs at station 9+40+ opposite the intake tower where the crest elevation is 113.7. This elevation is 1.3 feet below the anticipated settled top elevation of the crest and is only two-tenths (0.2') of a foot higher than the crest of the control section of the emergency spillway. Plate C-6 shows the profile of the dam as determined during the inspection. Photos 15, 17 and 23 show the crest of the dam.
- (4) Downstream Slope. The downstream slope is well vegetated with adapted grasses. No slumps, slides, cracks or abnormal deformations were observed on the slope. A few small trees are growing on the slope. No evidence of seepage was observed on the slope or along the toe of the slope. Measurements indicate that the slope was constructed according to the plans. Photos No. 15, 18, and 22 show the downstream slope.

c. Appurtenant Structures.

- (1) The principal spillway is uncontrolled and consists of a reinforced concrete box, chute and St. Anthony Falls type stilling basin located in the left abutment. Measurements indicate that it was constructed according to the plans shown in Appendix C. The forebay or inlet is well vegetated and open. Photos 3, 4, 5 and 7 show the forebay and overall spillway. The joint between the first and second sections (upstream) of the left sidewall is open about 0.75 inches from the top down about 3 feet as shown in Photo No. 6. The floor of the next to the last (downstream) section of the chute (Sec. D-6 on plans) is badly scaled across most of the bottom, as shown in Photos 9, 12 and 13. All of the lower set of weep holes in the floor section were discharging clear water. The last downstream sections of the side walls of the stilling basin (Sec. H-6 on plans)

are both out of vertical alignment. The top of the left wall is displaced inward about 3 inches. The top of the right wall is displaced inward about 1.5 inches. The misalignments of the sidewalls are shown in Photos 10 and 11.

- (2) The emergency spillway is uncontrolled and consists of a vegetated earth channel cut through the right abutment with a roadway crossing that serves as a control weir. The spillway is well vegetated with adapted grasses. Measurements indicate that the spillway was constructed essentially as planned. No slides or slumps were observed, and there was no evidence of significant erosion in the spillway. There was no evidence that this spillway has operated. As noted previously, if this emergency spillway operates, there will probably be flow over the low swag in the crest of the dam. Photos 25 and 26 show the emergency spillway.
 - (3) The drawdown facility for this dam is related entirely to providing water for the city water treatment plant through the intake tower. Two 8-inch cast iron pipe intake lines extend from the intake tower into the reservoir. These lines are shown on the plans at elevations of 105 and 95 and are manually controlled by operation of rising stem gate valves. The elevation of the lower line is estimated to be 15 feet \pm above the low point in the reservoir. Water is drawn from the intake tower into the filtration plant through an 8-inch cast iron pipe which is gate valve controlled within the plant. The volume of flow through this line is dependent upon the demand for potable water by the city.
- d. Reservoir Area. The area around the reservoir is well vegetated with grass. No slides were observed and there was no evidence of significant erosion around the water line of the reservoir. There was no evidence of heavy siltation. Photo No. 20 shows a portion of the reservoir.
 - e. Downstream Channel. The channel downstream from the principal spillway appears to be stable. Mr. Kuhnert reported that bed-rock is close to the surface in the outlet channel. A number of trees are growing in the channel between the highway bridge and the structure. Photos No. 5 and 28 show the principal spillway channel.

The channel for the emergency spillway is open and vegetated with grass. Discharge from the emergency spillway would probably encroach upon the toe of the dam and the filtration plant.

3.2 EVALUATION

The dam appears to be in reasonably good structural condition with no serious potential of failure. There were no indications of

seepage on the downstream slope or along the toe of the dam. The crest of the embankment is very irregular with one area about the same elevation as the emergency spillway. The crest elevation should be brought up to planned elevation. Deterioration of the riprap and erosion on the upstream slope could ultimately impair the integrity of the dam. Trees on the embankment should be removed under the guidance of a professional engineer experienced in the design and construction of dams. The open joints in the walls and the scaling in the floor of the principal spillway should be repaired to prevent further deterioration. Removal of trees in the principal spillway channel would improve the discharge characteristics of the structure. The dike that crosses the emergency spillway reduces the capacity of the spillway and consideration should be given to its removal.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

The pool level is controlled by rainfall, infiltration, evaporation, the capacity of the uncontrolled spillways, and the demand for city water.

4.2 MAINTENANCE OF DAM

Maintenance of the vegetated sections of the dam appears to be good. One of Mr. Kuhnert's men reported that the crest and slopes of the dam are mowed several times each year. Some effort has been made to supplement the riprap on the upstream slope, but additional repair and maintenance is needed. No apparent maintenance work has been done on the concrete spillway.

4.3 MAINTENANCE OF OPERATING FACILITIES

The operating facilities connected with the withdrawal of water from the reservoir and treating it for use by the city appeared to be well maintained.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

4.5 EVALUATION

Maintenance and repair should be done on the concrete spillway in order to prevent further deterioration. The same applies to the upstream slope of the dam.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

- a. Design Data. Plans for the 1954 reconstruction of the dam were furnished by the Hamilton City Water Department.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the USGS Polo and Winston, Missouri, 15 minute topographic quadrangle maps. The hydraulic computations for the spillway and dam over-topping discharge ratings were based on data collected in the field at the time of the field inspection. Hydraulic/Hydro-logic computations are attached as Appendix D of this report.
- c. Visual Observations.
 - (1) The concrete principal spillway is only in fair condition. As the photographs indicate, much of the joint filler in the side walls has slipped or fallen out entirely, some of the side wall sections are considerably out of line, and there are several areas on the floor that show spalling and scaling.
 - (2) The earthen spillway channel through the right abutment is open and well vegetated on both upstream and downstream sides of the roadway dike that now serves as the control section of the spillway. The construction plans (Plate C-2) show that the spillway channel was to be excavated to an elevation of 110.2. The dike was then to be constructed across the excavated channel with a finished top elevation of 113.5 (confirmed during inspection). The dike was evidently constructed in order to provide a vehicular crossing of the spillway and with the knowledge that if over-topped the dike would erode down to the channel elevation of 110.2 which would then be the control elevation of the spillway. The control elevation of this spillway was intended to be two-tenths of a foot higher than the control section of the concrete spillway constructed through the right abutment (110.2 as compared to 110.0). The elevation difference between the crest of the emergency spillway and the low point in the crest of the dam is only two-tenths of a foot as described in paragraph 3.1b.(3) of this report. Overtopping of the dam immediately above the filter house would occur very shortly after flow commenced through the emergency spillway.
 - (3) More riprap should be added to several areas on the upstream face of the dam.

- d. Overtopping Potential. The spillways are too small to pass the probable maximum flood without overtopping the dam. The spillways will pass 30 percent of the probable maximum flood as well as the 1 percent probability flood without overtopping. Overtopping is dangerous because the flow of water over the crest will erode the face of the dam and, if continued long enough, will breach the dam with sudden release of all of the impounded water into the downstream floodplain. The hydrologic capability of this dam would be greatly enhanced by removal of the dike crossing the emergency spillway and by increasing the height of the low areas of the dam to the planned elevation of 115.0.

The results of the routing through the dam are tabulated in regards to the following conditions:

<u>Frequency</u>	<u>Inflow Discharge c.f.s.</u>	<u>Outflow Discharge c.f.s.</u>	<u>Maximum Pool Elevation</u>	<u>Maximum Depth Over Dam Feet*</u>	<u>Duration Over Top Hours</u>
1/2 PMF	5,660	4,080	114.7	1.0	2
PMF	11,300	10,500	115.9	2.2	5
0.3 PMF	3,750	2,260	113.7	0.0	-

*Minimum Top of Dam Elevation - 113.7

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard potential rating and an intermediate size. Therefore, the PMF is the test for the adequacy of the dam and its spillways.

The estimated damage zone is described in Paragraph 1.2d in this report.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. There was no visual evidence such as slumps, slides, cracks or abnormal deformations to indicate structural instability of this dam. No evidence of seepage was observed either on the downstream slope or along the toe of the dam. Based on visual inspection and measurements the dam is considered to be structurally stable against shear and seepage failures. The area of the dam in which the sag in the crest exists (station 7+00 to 13+00) shows no evidence of abnormal deformation in the downstream slope. A cross section survey made during the inspection shows a slope of 1V on 2.3+H as compared to 1V on 2.25H as shown on the construction plans for the area upstream from the filter house (Plates C-7 and C-2). The embankment through the sag area has evidently settled more than originally anticipated. Reconstruction of the crest of the dam through the sag area to a uniform elevation of 115.0 (as planned) would minimize the danger of overtopping. The erosion of the upstream slope and tree growth on the embankment, if allowed to progress, could ultimately impair the integrity of the dam. The effects of overtopping on the erosional stability of the dam are not known. Continued deterioration of the concrete floor and the wall joints of the principal spillway should be halted.
- b. Design and Construction Data. Design data were available from the City of Hamilton. Measurements indicate that the structure was constructed according to the Kenneth H. Larkin and Associates plans, which are included in Appendix C. Seepage and slope stability analyses comparable to the "Recommended Guidelines for Safety Inspection of Dams" were not available. This is considered a deficiency.
- c. Operating Records. The operating facilities of this dam are used as needed to fulfill the demand for city water.
- d. Post Construction Changes. The inspection team is not aware of any post construction changes for this dam since the 1954 construction.
3. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of the magnitude predicted in this area is not expected to cause structural failure of this dam or the concrete spillway.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

- a. Safety. This dam is in reasonably good structural condition. Analyses presented in Section 5 indicate that the spillways are not adequate to pass the Probable Maximum Flood without overtopping the dam. Overtopping is dangerous because the flow of water over the crest will erode the face of the dam and, if continued long enough, will breach the dam with sudden release of all of the impounded water into the downstream floodplain. Overtopping of this dam will occur almost directly above the city water treatment plant.

Based on visual inspection and measurements this dam is considered to be structurally stable against shear and seepage failures. Erosion on the upstream slope and tree growth on the embankment could impair the integrity of the structure if left uncontrolled. Deterioration of portions of the concrete spillway could ultimately require major repairs of the structure if remedial measures are not performed. Removal of trees in the principal spillway channel would improve the hydraulic efficiency of the structure. The hydrologic capabilities of the dam would be greatly enhanced by removal of the dike in the emergency spillway and by increasing the height of the low sections of the dam to be planned elevation of 115.0

- b. Adequacy of Information. The conclusions in this report are based upon performance history, visual observations, and data made available by the city. Seepage and stability analyses comparable to the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Urgency. The measures recommended in paragraph 7.2b should be accomplished in the near future. The item recommended in paragraph 7.2a should be pursued on a high priority basis.
- d. Necessity for Further Investigations. The additional studies and analyses recommended in paragraph 7.2b should be accomplished by the owner in the near future.
- e. Seismic Stability. This dam is located in Seismic Zone I. An earthquake of this magnitude is not expected to be hazardous to this dam. It is recommended, however, that the prescribed seismic loading for Seismic Zone I be applied in any stability analyses performed for this dam.

7.2 REMEDIAL MEASURES


The following remedial measures and maintenance procedures are recommended. All remedial measures should be performed under the guidance of a registered professional engineer experienced in the design and construction of earth dams.

- a. Alternatives. The spillway size and/or the height of dam should be increased to pass the probable maximum flood without overtopping the dam.

b. Operation and Maintenance Procedures.

- (1) Seepage and stability analyses comparable to the requirements of the recommended guidelines should be performed by a professional engineer experienced in the design and construction of dams.
- (2) Trees should be removed from the embankment slopes and the outlet channel of the concrete spillway. This should be done under the guidance of a professional engineer experienced in the design and construction of dams.
- (3) The eroded areas of the upstream slope should be repaired and additional riprap provided in order to prevent further erosion and deterioration of the slope. This should be done under the guidance of a professional engineer experienced in the design and construction of dams.
- (4) The last downstream sections of the concrete stilling basin should be monitored periodically to determine whether the inward displacement at the top of the walls is increasing. Remedial measures may be required.
- (5) The joints in the concrete spillway structure should be checked for missing joint filler. Open joints should be resealed.
- (6) The areas of the floor section and the walls of the concrete spillway structure where scaling has occurred should be repaired.
- (7) The present practice of mowing the embankment is excellent and should be continued.
- (8) A program of periodic inspection and maintenance should be initiated. Records of inspection should be made a part of the project file.

APPENDIX A
MAPS



Scale in feet
3000 0 3000 6000 9000 12000

Contour Interval - 20'




VICINITY TOPOGRAPHY

HAMILTON CITY WATER PLANT DAM

CALDWELL COUNTY, MISSOURI

MO. 10261

PLATE A-1



APPENDIX B
PHOTOGRAPHS



HAMILTON CITY WATER PLANT DAM
CALDWELL COUNTY, MISSOURI
MO 10261

PHOTO INDEX

PLATE B-1



PHOTO NO. 2 - OVERVIEW TAKEN FROM UPPER LEFT SIDE.



PHOTO NO. 3 - ENTRANCE CHANNEL TO PRINCIPAL SPILLWAY. LOOKING
DOWNSTREAM TO CONCRETE CHUTE.




PHOTO NO. 4 - VIEW OF PRINCIPAL SPILLWAY CHUTE TAKEN FROM LEFT SIDE.




PHOTO NO. 5 - LOOKING DOWN PRINCIPAL SPILLWAY CHUTE FROM LEFT SIDE.



PHOTO NO. 6 - VIEW OF
OPENING OF FIRST JOINT
ON LEFT SIDE OF PRINCIPAL
SPILLWAY CHUTE.



PHOTO NO. 7 - VIEW OF FOREBAY OF PRINCIPAL SPILLWAY CHUTE
TAKEN FROM LEFT SIDE.




PHOTO NO. 8 - DOWNSTREAM VIEW OF PRINCIPAL SPILLWAY CHUTE.




PHOTO NO. 9 - CONCRETE SCALING AT SECOND JOINT ON LEFT SIDE OF PRINCIPAL SPILLWAY CHUTE.



PHOTO NO. 10 - MISALIGN-
MENT OF DOWNSTREAM SECTION
OF SPILLWAY ON LEFT SIDE.




PHOTO NO. 11 - MISALIGN-
MENT OF DOWNSTREAM SECTION
OF SPILLWAY ON RIGHT SIDE.



PHOTO NO. 12 - CONCRETE SCALING UPSTREAM OF CHUTE BLOCKS ON LEFT SIDE OF CENTERLINE.



PHOTO NO. 13 - CONCRETE SCALING UPSTREAM OF CHUTE BLOCKS ON RIGHT SIDE OF CENTERLINE.



PHOTO NO. 14 - UPSTREAM FACE TAKEN FROM END OF LEFT LEG OF DAM.



PHOTO NO. 15 - CREST AND DOWNSTREAM SLOPE OF LEFT LEG OF DAM.



PHOTO NO. 16 - UPSTREAM SLOPE OF MAIN DAM TAKEN FROM LEFT LEG OF DAM.



PHOTO NO. 17 - CREST OF MAIN DAM TAKEN FROM LEFT AT POINT OF CURVATURE WITH LEFT LEG.



PHOTO NO. 18 - DOWNSTREAM SLOPE OF MAIN DAM TAKEN FROM LEFT.



PHOTO NO. 19 - UPSTREAM SLOPE OF LEFT END OF MAIN DAM SHOWING
EROSION AND DETERIORATION OF RIPRAP.



PHOTO NO. 20 - VIEW UPSTREAM WITH INTAKE TOWER TO WATER TREATMENT PLANT
IN FOREGROUND.



PHOTO NO. 21 - VIEW DOWNSTREAM TAKEN FROM INTAKE TOWER LOCATION. BRIDGE
AT EXTREME LEFT SPANS OUTLET CHANNEL.



PHOTO NO. 22 - DOWNSTREAM SLOPE TAKEN FROM RIGHT.



PHOTO NO. 23 - CREST OF MAIN DAM TAKEN FROM RIGHT. MAN IN BACKGROUND STANDING IN SAG OVER OR NEAR PIPE FROM INTAKE TOWER TO WATER TREATMENT PLANT.



PHOTO NO. 24 - VERTICAL DROP AND EROSION OF UPSTREAM FACE NEAR RIGHT END.



PHOTO NO. 25 - VIEW UPSTREAM IN EMERGENCY SPILLWAY. DIKE AND ROAD CROSSING SPILLWAY SHOWS IN CENTER OF PICTURE.



PHOTO NO. 26 - VIEW DOWNSTREAM IN EMERGENCY SPILLWAY.



PHOTO NO. 27 - VIEW OF UPSTREAM FACE TAKEN FROM RIGHT END.





PHOTO NO. 28 - VIEW OF PRINCIPAL SPILLWAY CHUTE AND DOWNSTREAM CHANNEL
TAKEN FROM HIGHWAY BRIDGE.



PHOTO NO. 29 - HOUSE IN FLOODPLAIN, 2 MILES DOWNSTREAM OF DAM.


APPENDIX C
PROJECT PLATES





Present Lake Level
Elev. 1000

Sandy Brown Clay



AUGER TEST HOLES ALONG

Note: See sheet 2 and 3 for details

NOTE:
Design for Reservoir Site is to be in accordance with the Specifications

New Lake - Elev. 10 - Area Approx 73 Acres

Old Lake - Elev. 90 - Area Approx 27 Acres

East Lake - Elev. 100 - Area Approx 10 Acres

Test Hole #122

Test Hole #121


Lake Shore Borrow

Test Hole #120

Borrow Pit
Spillway Excavation

- 1. 1/4"
- 2. 1/2"
- 3. 1"
- 4. 2"
- 5. 4"
- 6. 8"
- 7-10

Project Lake Erie
Elev. 1000



AUGER TEST HOLES ALONG LINE

Scale 1" = 10'


Note: See sheet 8 for plan view and details.

NOTE:
Crossing for the right side of the
road is shown in the plan view.

New Lake Erie - Elev. 1000 - Approx. 73 Acres

Project Lake Erie - Elev. 1000 - Approx. 27 Acres

Project Lake Erie - Elev. 1000 - Approx. 27 Acres




LIST OF

1. TITLE SHEET
2. MAP SHEET
3. LAYOUT SHEET
4. DAM SECTION
5. DETAILS AND
6. SPILLWAY
- 7-10. CROSS SECTION

Drainage Capacity

Excavation may be affected in phase
due to direction of flow



RESULTS

SEP 21 1961 - 10 days

Ex: 3 6 Core Core wall
Sto 6+65 to Stn 12+50.4


GENERAL NOTES

[illegible]

1. The first one is the
2. The second one is the
3. The third one is the

PARK

M.S. HIGHWAY



Lgt. at Main piers
Centerline bridge
110' 0" at 100'

Note:
1. All concrete
work shall be done
in accordance with
the 1960 Bridge
Specs. B35 to Supp.
2. C.I. Standard
mainline steps
shall be used.

SECTION 1

SECTION 2

SECTION 3

PLAN
MANHOLE
Scale - 1/4" = 1'-0"

A = 40'-0"
T = 36'-0"
L = 65'-2"
R = 63'-4"

Remove Conc
Steps

Remove
Existing
Spillway

Compacted fill
Material shall be 3:1
to 1. Elev.
95.0' to 96.0'.
Filled to E-W line.
Block fill in
hole on St. 4.

Remove masonry
up to top of the
pier.

Power Pole
to be moved
to the right
of others.


Approach
fill with compacted
fill.

Fill hole to be
filled to same level
as the other hole.

Concrete shall be
cast with 10% rock
in place.

Remove unstable soil
and fill as directed
by engineer. Replace with
stable soil to base of
previous bracket. Base of
bracket to be Elev 81 here.

Continue for shall lower and protect.
C.E. will make any necessary alterations.



Impervious layer

2. 1/2" x 1/2" x 1/2" 3/4" Sand 6"
3. 1/2" x 1/2" x 1/2" 3/4" Crushed rock
4. 1/2" x 1/2" x 1/2" 3/4" West End
5. 1/2" x 1/2" x 1/2" 3/4" at NE corner
6. 1/2" x 1/2" x 1/2" 3/4" at NE corner

0° Typical where
wrap is placed
on earth face.

1. 1/2" x 1/2" x 1/2" 3/4" Sand 6"
2. 1/2" x 1/2" x 1/2" 3/4" Crushed rock
3. 1/2" x 1/2" x 1/2" 3/4" West End
4. 1/2" x 1/2" x 1/2" 3/4" at NE corner
5. 1/2" x 1/2" x 1/2" 3/4" at NE corner

1. 1/2" x 1/2" x 1/2" 3/4" Sand 6"
2. 1/2" x 1/2" x 1/2" 3/4" Crushed rock
3. 1/2" x 1/2" x 1/2" 3/4" West End
4. 1/2" x 1/2" x 1/2" 3/4" at NE corner
5. 1/2" x 1/2" x 1/2" 3/4" at NE corner

1. 1/2" x 1/2" x 1/2" 3/4" Sand 6"
2. 1/2" x 1/2" x 1/2" 3/4" Crushed rock
3. 1/2" x 1/2" x 1/2" 3/4" West End
4. 1/2" x 1/2" x 1/2" 3/4" at NE corner
5. 1/2" x 1/2" x 1/2" 3/4" at NE corner

1. 1/2" x 1/2" x 1/2" 3/4" Sand 6"
2. 1/2" x 1/2" x 1/2" 3/4" Crushed rock
3. 1/2" x 1/2" x 1/2" 3/4" West End
4. 1/2" x 1/2" x 1/2" 3/4" at NE corner
5. 1/2" x 1/2" x 1/2" 3/4" at NE corner

1. 1/2" x 1/2" x 1/2" 3/4" Sand 6"
2. 1/2" x 1/2" x 1/2" 3/4" Crushed rock
3. 1/2" x 1/2" x 1/2" 3/4" West End
4. 1/2" x 1/2" x 1/2" 3/4" at NE corner
5. 1/2" x 1/2" x 1/2" 3/4" at NE corner

Existing
Silt line
Elev. 10.00

Silt line
and earth face
Elev. 10.00

Typical for entire length
of present dam and core
wall. Slo. 0.65 to 12.30

2.0°
East Core
Core wall

Reference line for
determination of
silt line
Elev. 10.00

0.5

50%

2 D.P. - 50' x 10' 6"
 10' 4" x 3' 6" USED ROCK
 600' 11' 3" West End
 100' 11' 3" at NE corner
 100' 11' 3"

CONTRACTED FILL

CUS PLANKED SETTLING BASING

Scale 1" = 25'

CONTRACTED FILL
 10' 4" x 3' 6" USED ROCK

CONTRACTED FILL

CONTRACTED FILL

Slope Varies See Plan, Sht. E

76' 0"

50' 0"

(Mass. North - 1000')

Line 92

100' 11' 3" at NE corner
 100' 11' 3"

Remove old spillway
 and use for Rock Fill
 on riprap.

TYPICAL SECTION AT EXISTING SPILLWAY

Line 92
 100' 11' 3" at NE corner
 100' 11' 3"

Line 92
 100' 11' 3" at NE corner
 100' 11' 3"

Quarry
 100' 11' 3" at NE corner
 100' 11' 3"

50' 0"

Line 92

COMPACTED FILL

Slope varies See Plan, Sht. 2

76.0

50'-0"

(N. 1/2 S. 1/4 - 34.0)

1.00 96

Remove old spillway
and use for Rock Fill
or riprap.

Waterway

DETAIL SECTION AT EXISTING RAILWAY

See Specifications for
Slope, Sht. 2

Note in Eastern
Existing Spillway

Quarry Run
100 to 150 ft.
with gravel



12" V.C.P. Drain
in concrete
see DWG. 3.

SECTION C-5
Scale 1/4" = 1'-0"



SECTION I-5
Scale 1/4" = 1'-0"


Notes:
Exposure and Re-
inforcement De-
sign of concrete
to be in accordance
with A.C.I. 318-63.



SECTION K-5
Scale 1/4" = 1'-0"



TYPICAL
DETAIL FOR




Flow into exposure
and up while Uniformly
compressing fill short
in front of
E 94'-4"



SECTION N-5
Scale 1/4" = 1'-0"


Notes:
1. All work shall
be in accordance
with A.C.I. 318-63.

SECTION O-5
Scale 1/4" = 1'-0"






SECTION P-5
Scale 1/4" = 1'-0"

DETAIL








EXISTING FILTRATION PLANT Scale 1/4" = 1'-0"






TOP VIEW OF INTAKE


Area Elev 189.7











CROSS-SECTION OF DAM AT STA. 10+30

Scale: 1"=10'


APPENDIX D
HYDRAULIC AND HYDROLOGIC DATA


HYDROLOGIC COMPUTATIONS

1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs (See this Section).
 - a. Forty-eight hour, one percent probabilistic rainfall for the dam location was taken from the data for the rainfall station at Chillicothe, MO. as supplied by the St. Louis District, Corps of Engineers per their letter dated 4 March 1980. The forty-eight hour probable maximum precipitation was taken from the curves of Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis policy and guidance for hydraulics and hydrology.
 - b. Drainage area = 1.78 square miles (1,141 acres).
 - c. Time of concentration of runoff = 56 minutes (computed from the "Kirpich" formula). This compares to 58 minutes as computed from California Culverts Practice, California Highways and Public Works.
 - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the one percent probabilistic precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the invert of the principal spillway.
 - e. The total forty-eight hour storm duration losses for the one percent probabilistic storm were 2.28 inches. The total losses for the PMF storm were 1.02 inches. These data are based on SCS runoff curve No. 81 and No. 92 for antecedent moisture conditions SCS AMC II and AMC III respectively. The watershed is composed of primarily SCS soil groups C and D (Lagonda-Lamoni-Adair Soil Association). The watershed is approximately 60% under cultivation in row crops, small grain, and legumes on partially contoured or terraced land. The remainder is pasture and woodland.
 - f. Average soil loss rates = 0.02 inch per hour approximately (For PMF storm, AMC III).
2. The combined discharge rating consisted of three components: the flow through the principal spillway, the flow through the emergency spillway and the flow going over the top of the dam.
 - a. The principal spillway (concrete chute) rating was developed using the Corps of Engineers Water Surface Profile HEC-2 computer program assuming critical depth at the chute weir-crest.
 - b. The emergency spillway (earthen channel with dike) rating was developed using road-overflow methods and coefficients founds in USGS TWRI, Bk 3, Ch. A5 "Measurement of Peak Discharge at Dams by Indirect Methods".


- c. The flows over the dam were determined by using the dam overtopping analyses (irregular top of dam) within the HEC-1 (Dam Safety Version) program.
3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The input, output and plotted hydrographs are attached in this Section.

HAMILTON CITY
WATER PLANT DAM
NO. 12, NO. 10261
OUTFLOW-RATING
CURVES





(PLANS)



[illegible][illegible]

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79

RUN DATE= 80/07/25.
 TIME= 13.29.56.

HAMILTON CITY WATER PLANT DAM/NO ID NO 10261
 SAFETY ANALYSIS OF DAM OVERTOPPING USING ASSIGNED FLOOD FREQUENCIES
 H & H ANALYSIS BY ROUTING PMF RATIOS THRU THE RESERVOIR

JOB SPECIFICATION									
NQ	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
288	0	10	0	0	0	0	0	3	0
			JOPER	NMT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

NPLAN= 1 NRTIO= 8 LRTIO= 1
 RTIOS= .05 .10 .15 .20 .25 .50 .75 1.00

SUB-AREA RUNOFF COMPUTATION

CALCULATION OF INFLOW HYDRO TO RESERVOIR 10261

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	TAUTO
000001	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IHYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOM	ISAME	LOCAL
1	2	1.78	0.00	1.78	1.00	0.000	0	1	0

PRECIP DATA

SPFE	PM5	R6	R12	R24	R48	R72	R96
0.00	24.20	102.00	121.00	130.00	140.00	0.00	0.00

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERATN	STKRS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	-1.00	-92.00	0.00	0.00

CURVE NO = -92.00 WEINSS = -1.00 EFFECT CN = 92.00

UNIT HYDROGRAPH DATA
 TC= 0.00 LAG= .56

RECESSION DATA

STRTQ= 0.00 QRCSN= -.01 RTIOR= 1.00

UNIT HYDROGRAPH 19 END OF PERIOD ORDINATES, IC= 0.00 HOURS, LAG= .56 VOL= 1.00
 204. 670. 1205. 1331. 1157. 829. 515. 342. 227. 148.
 97. 64. 42. 27. 18. 13. 8. 5. 1.

END-OF-PERIOD FLOW

MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1.01	1.10	1	.00	0.00	.00	0.	1.02	1.10	145	.02	.02	.00	22.
1.01	1.20	2	.00	0.00	.00	0.	1.02	1.20	146	.02	.02	.00	32.
1.01	1.30	3	.00	0.00	.00	0.	1.02	1.30	147	.02	.02	.00	59.
1.01	1.40	4	.00	0.00	.00	0.	1.02	1.40	148	.02	.02	.00	85.
1.01	1.50	5	.00	0.00	.00	0.	1.02	1.50	149	.02	.02	.00	108.
1.01	1.00	6	.00	0.00	.00	0.	1.02	1.00	150	.02	.02	.00	125.
1.01	1.10	7	.00	0.00	.00	0.	1.02	1.10	151	.02	.02	.00	135.
1.01	1.20	8	.00	0.00	.00	0.	1.02	1.20	152	.02	.02	.00	142.
1.01	1.30	9	.00	0.00	.00	0.	1.02	1.30	153	.02	.02	.00	147.
1.01	1.40	10	.00	0.00	.00	0.	1.02	1.40	154	.02	.02	.00	150.
1.01	1.50	11	.00	0.00	.00	0.	1.02	1.50	155	.02	.02	.00	152.
1.01	2.00	12	.00	0.00	.00	0.	1.02	2.00	156	.02	.02	.00	153.
1.01	2.10	13	.00	0.00	.00	0.	1.02	2.10	157	.02	.02	.00	154.
1.01	2.20	14	.00	0.00	.00	0.	1.02	2.20	158	.02	.02	.00	155.
1.01	2.30	15	.00	0.00	.00	0.	1.02	2.30	159	.02	.02	.00	155.
1.01	2.40	16	.00	0.00	.00	0.	1.02	2.40	160	.02	.02	.00	156.
1.01	2.50	17	.00	0.00	.00	0.	1.02	2.50	161	.02	.02	.00	156.
1.01	3.00	18	.00	0.00	.00	0.	1.02	3.00	162	.02	.02	.00	156.
1.01	3.10	19	.00	0.00	.00	0.	1.02	3.10	163	.02	.02	.00	156.
1.01	3.20	20	.00	0.00	.00	0.	1.02	3.20	164	.02	.02	.00	157.
1.01	3.30	21	.00	0.00	.00	0.	1.02	3.30	165	.02	.02	.00	157.
1.01	3.40	22	.00	0.00	.00	0.	1.02	3.40	166	.02	.02	.00	157.
1.01	3.50	23	.00	0.00	.00	0.	1.02	3.50	167	.02	.02	.00	157.
1.01	4.00	24	.00	0.00	.00	0.	1.02	4.00	168	.02	.02	.00	157.
1.01	4.10	25	.00	0.00	.00	0.	1.02	4.10	169	.02	.02	.00	157.
1.01	4.20	26	.00	0.00	.00	0.	1.02	4.20	170	.02	.02	.00	157.
1.01	4.30	27	.00	0.00	.00	0.	1.02	4.30	171	.02	.02	.00	158.
1.01	4.40	28	.00	0.00	.00	0.	1.02	4.40	172	.02	.02	.00	158.
1.01	4.50	29	.00	0.00	.00	0.	1.02	4.50	173	.02	.02	.00	158.
1.01	5.00	30	.00	0.00	.00	0.	1.02	5.00	174	.02	.02	.00	158.
1.01	5.10	31	.00	0.00	.00	0.	1.02	5.10	175	.02	.02	.00	158.
1.01	5.20	32	.00	0.00	.00	0.	1.02	5.20	176	.02	.02	.00	158.
1.01	5.30	33	.00	0.00	.00	0.	1.02	5.30	177	.02	.02	.00	158.
1.01	5.40	34	.00	0.00	.00	0.	1.02	5.40	178	.02	.02	.00	158.
1.01	5.50	35	.00	0.00	.00	0.	1.02	5.50	179	.02	.02	.00	158.
1.01	6.00	36	.00	0.00	.00	0.	1.02	6.00	180	.02	.02	.00	159.
1.01	6.10	37	.01	0.00	.01	0.	1.02	6.10	181	.13	.12	.01	179.
1.01	6.20	38	.01	0.00	.01	0.	1.02	6.20	182	.13	.12	.01	252.
1.01	6.30	39	.01	0.00	.01	0.	1.02	6.30	183	.13	.12	.01	365.
1.01	6.40	40	.01	0.00	.01	0.	1.02	6.40	184	.13	.12	.00	497.
1.01	6.50	41	.01	0.00	.01	0.	1.02	6.50	185	.13	.12	.00	612.
1.01	7.00	42	.01	0.00	.01	0.	1.02	7.00	186	.13	.12	.00	646.
1.01	7.10	43	.01	0.00	.01	0.	1.02	7.10	187	.13	.12	.00	748.
1.01	7.20	44	.01	0.00	.01	0.	1.02	7.20	188	.13	.12	.00	783.
1.01	7.30	45	.01	0.00	.01	0.	1.02	7.30	189	.13	.12	.00	807.
1.01	7.40	46	.01	0.00	.01	0.	1.02	7.40	190	.13	.12	.00	824.
1.01	7.50	47	.01	0.00	.01	0.	1.02	7.50	191	.13	.12	.00	835.
1.01	8.00	48	.01	0.00	.01	0.	1.02	8.00	192	.13	.12	.00	842.
1.01	8.10	49	.01	0.00	.01	0.	1.02	8.10	193	.13	.12	.00	848.
1.01	8.20	50	.01	0.00	.01	1.	1.02	8.20	194	.13	.12	.00	852.
1.01	8.30	51	.01	0.00	.01	1.	1.02	8.30	195	.13	.12	.00	855.
1.01	8.40	52	.01	0.00	.01	2.	1.02	8.40	196	.13	.13	.00	857.
1.01	8.50	53	.01	0.00	.01	3.	1.02	8.50	197	.13	.13	.00	859.
1.01	9.00	54	.01	0.00	.01	4.	1.02	9.00	198	.13	.13	.00	861.
1.01	9.10	55	.01	0.00	.01	5.	1.02	9.10	199	.13	.13	.00	862.
1.01	9.20	56	.01	0.00	.01	7.	1.02	9.20	200	.13	.13	.00	862.
1.01	9.30	57	.01	0.00	.01	8.	1.02	9.30	201	.13	.13	.00	863.
1.01	9.40	58	.01	0.00	.01	8.	1.02	9.40	202	.13	.13	.00	864.
1.01	9.50	59	.01	0.00	.01	10.	1.02	9.50	203	.13	.13	.00	865.
1.01	10.00	60	.01	0.00	.01	11.	1.02	10.00	204	.13	.13	.00	865.

1.01	10.10	61	.01	.00	.01	13.	1.02	10.10	205	.13	.13	.00	866.
1.01	10.20	62	.01	.00	.01	14.	1.02	10.20	206	.13	.13	.00	866.
1.01	10.30	63	.01	.00	.01	15.	1.02	10.30	207	.13	.13	.00	867.
1.01	10.40	64	.01	.00	.01	16.	1.02	10.40	208	.13	.13	.00	868.
1.01	10.50	65	.01	.00	.01	17.	1.02	10.50	209	.13	.13	.00	868.
1.01	11.00	66	.01	.00	.01	18.	1.02	11.00	210	.13	.13	.00	869.
1.01	11.10	67	.01	.00	.01	19.	1.02	11.10	211	.13	.13	.00	869.
1.01	11.20	68	.01	.00	.01	20.	1.02	11.20	212	.13	.13	.00	869.
1.01	11.30	69	.01	.00	.01	21.	1.02	11.30	213	.13	.13	.00	870.
1.01	11.40	70	.01	.00	.01	21.	1.02	11.40	214	.13	.13	.00	870.
1.01	11.50	71	.01	.00	.01	22.	1.02	11.50	215	.13	.13	.00	871.
1.01	12.00	72	.01	.00	.01	23.	1.02	12.00	216	.13	.13	.00	871.
1.01	12.10	73	.03	.01	.02	26.	1.02	12.10	217	.41	.41	.00	928.
1.01	12.20	74	.03	.01	.02	33.	1.02	12.20	218	.41	.41	.00	1117.
1.01	12.30	75	.03	.01	.02	45.	1.02	12.30	219	.41	.41	.00	1456.
1.01	12.40	76	.03	.02	.02	60.	1.02	12.40	220	.41	.41	.00	1831.
1.01	12.50	77	.03	.02	.02	74.	1.02	12.50	221	.41	.41	.00	2157.
1.01	13.00	78	.03	.02	.01	86.	1.02	13.00	222	.41	.41	.00	2391.
1.01	13.10	79	.04	.02	.02	96.	1.02	13.10	223	.49	.49	.00	2554.
1.01	13.20	80	.04	.02	.02	106.	1.02	13.20	224	.49	.49	.00	2706.
1.01	13.30	81	.04	.02	.01	118.	1.02	13.30	225	.49	.49	.00	2870.
1.01	13.40	82	.04	.02	.01	129.	1.02	13.40	226	.49	.49	.00	3022.
1.01	13.50	83	.04	.02	.01	140.	1.02	13.50	227	.49	.49	.00	3145.
1.01	14.00	84	.04	.03	.01	149.	1.02	14.00	228	.49	.49	.00	3233.
1.01	14.10	85	.05	.03	.01	158.	1.02	14.10	229	.62	.61	.00	3313.
1.01	14.20	86	.05	.03	.01	169.	1.02	14.20	230	.62	.62	.00	3432.
1.01	14.30	87	.05	.03	.01	183.	1.02	14.30	231	.62	.62	.00	3605.
1.01	14.40	88	.05	.04	.01	197.	1.02	14.40	232	.62	.62	.00	3786.
1.01	14.50	89	.05	.04	.01	210.	1.02	14.50	233	.62	.62	.00	3939.
1.01	15.00	90	.05	.04	.01	221.	1.02	15.00	234	.62	.62	.00	4049.
1.01	15.10	91	.04	.03	.01	229.	1.02	15.10	235	.56	.56	.00	4106.
1.01	15.20	92	.07	.06	.02	238.	1.02	15.20	236	.94	.94	.00	4191.
1.01	15.30	93	.13	.11	.02	266.	1.02	15.30	237	1.69	1.69	.00	4559.
1.01	15.40	94	.32	.27	.05	360.	1.02	15.40	238	4.22	4.21	.01	5975.
1.01	15.50	95	.09	.08	.01	523.	1.02	15.50	239	1.22	1.22	.00	8411.
1.01	16.00	96	.06	.05	.01	682.	1.02	16.00	240	.75	.75	.00	10751.
1.01	16.10	97	.04	.04	.01	727.	1.02	16.10	241	.58	.58	.00	11312.
1.01	16.20	98	.04	.04	.00	673.	1.02	16.20	242	.58	.58	.00	10367.
1.01	16.30	99	.04	.04	.00	568.	1.02	16.30	243	.58	.58	.00	8666.
1.01	16.40	100	.04	.04	.00	466.	1.02	16.40	244	.58	.58	.00	7045.
1.01	16.50	101	.04	.04	.00	400.	1.02	16.50	245	.58	.58	.00	5999.
1.01	17.00	102	.04	.04	.00	357.	1.02	17.00	246	.58	.58	.00	5307.
1.01	17.10	103	.03	.03	.00	327.	1.02	17.10	247	.45	.45	.00	4820.
1.01	17.20	104	.03	.03	.00	303.	1.02	17.20	248	.45	.45	.00	4437.
1.01	17.30	105	.03	.03	.00	281.	1.02	17.30	249	.45	.45	.00	4091.
1.01	17.40	106	.03	.03	.00	262.	1.02	17.40	250	.45	.45	.00	3798.
1.01	17.50	107	.03	.03	.00	247.	1.02	17.50	251	.45	.45	.00	3570.
1.01	18.00	108	.03	.03	.00	238.	1.02	18.00	252	.45	.45	.00	3413.
1.01	18.10	109	.00	.00	.00	226.	1.02	18.10	253	.04	.04	.00	3231.
1.01	18.20	110	.00	.00	.00	202.	1.02	18.20	254	.04	.04	.00	2885.
1.01	18.30	111	.00	.00	.00	164.	1.02	18.30	255	.04	.04	.00	2334.
1.01	18.40	112	.00	.00	.00	122.	1.02	18.40	256	.04	.04	.00	1745.
1.01	18.50	113	.00	.00	.00	87.	1.02	18.50	257	.04	.04	.00	1245.
1.01	19.00	114	.00	.00	.00	63.	1.02	19.00	258	.04	.04	.00	891.
1.01	19.10	115	.00	.00	.00	47.	1.02	19.10	259	.04	.04	.00	671.
1.01	19.20	116	.00	.00	.00	37.	1.02	19.20	260	.04	.04	.00	526.
1.01	19.30	117	.00	.00	.00	30.	1.02	19.30	261	.04	.04	.00	429.
1.01	19.40	118	.00	.00	.00	26.	1.02	19.40	262	.04	.04	.00	366.
1.01	19.50	119	.00	.00	.00	23.	1.02	19.50	263	.04	.04	.00	325.
1.01	20.00	120	.00	.00	.00	21.	1.02	20.00	264	.04	.04	.00	298.
1.01	20.10	121	.00	.00	.00	20.	1.02	20.10	265	.04	.04	.00	280.
1.01	20.20	122	.00	.00	.00	19.	1.02	20.20	266	.04	.04	.00	269.

1.01	20.30	123	.00	.00	.00	18.	1.02	20.30	267	.04	.04	.00	262.
1.01	20.40	124	.00	.00	.00	18.	1.02	20.40	268	.04	.04	.00	256.
1.01	20.50	125	.00	.00	.00	18.	1.02	20.50	269	.04	.04	.00	253.
1.01	21.00	126	.00	.00	.00	18.	1.02	21.00	270	.04	.04	.00	251.
1.01	21.10	127	.00	.00	.00	18.	1.02	21.10	271	.04	.04	.00	250.
1.01	21.20	128	.00	.00	.00	18.	1.02	21.20	272	.04	.04	.00	250.
1.01	21.30	129	.00	.00	.00	18.	1.02	21.30	273	.04	.04	.00	250.
1.01	21.40	130	.00	.00	.00	18.	1.02	21.40	274	.04	.04	.00	250.
1.01	21.50	131	.00	.00	.00	18.	1.02	21.50	275	.04	.04	.00	250.
1.01	22.00	132	.00	.00	.00	18.	1.02	22.00	276	.04	.04	.00	250.
1.01	22.10	133	.00	.00	.00	18.	1.02	22.10	277	.04	.04	.00	250.
1.01	22.20	134	.00	.00	.00	18.	1.02	22.20	278	.04	.04	.00	250.
1.01	22.30	135	.00	.00	.00	18.	1.02	22.30	279	.04	.04	.00	250.
1.01	22.40	136	.00	.00	.00	18.	1.02	22.40	280	.04	.04	.00	250.
1.01	22.50	137	.00	.00	.00	18.	1.02	22.50	281	.04	.04	.00	250.
1.01	23.00	138	.00	.00	.00	18.	1.02	23.00	282	.04	.04	.00	250.
1.01	23.10	139	.00	.00	.00	18.	1.02	23.10	283	.04	.04	.00	250.
1.01	23.20	140	.00	.00	.00	18.	1.02	23.20	284	.04	.04	.00	250.
1.01	23.30	141	.00	.00	.00	18.	1.02	23.30	285	.04	.04	.00	250.
1.01	23.40	142	.00	.00	.00	18.	1.02	23.40	286	.04	.04	.00	250.
1.01	23.50	143	.00	.00	.00	18.	1.02	23.50	287	.04	.04	.00	250.
1.02	0.00	144	.00	.00	.00	18.	1.03	0.00	288	.04	.04	.00	250.
SUM 33.88 32.86 1.02 225730.										1.861.11.835.11 26.11 6391.961			

CES	11312.	PEAK	4591.	24-HOUR	1490.	72-HOUR	783.	TOTAL VOLUME	225601.
CMS	320.		130.		42.		22.		6380.
INCHES			23.95		31.09		32.69		32.69
MM			608.33		789.61		830.45		830.45
AC-FT			2276.		2955.		3107.		3107.
THOUS CU M			2808.		3645.		3833.		3833.

HYDROGRAPH AT STA000001 FOR PLAN 1. RTIO 1

CES	566.	PEAK	230.	24-HOUR	74.	72-HOUR	39.	TOTAL VOLUME	11280.
CMS	16.		6.		2.		1.		319.
INCHES			1.20		1.55		1.63		1.63
MM			30.42		39.48		41.52		41.52
AC-FT			114.		148.		155.		155.
THOUS CU M			140.		182.		192.		192.

HYDROGRAPH AT STA000001 FOR PLAN 1. RTIO 2

CES	1131.	PEAK	459.	24-HOUR	149.	72-HOUR	78.	TOTAL VOLUME	22560.
CMS	32.		13.		4.		2.		639.
INCHES			2.39		3.11		3.27		3.27
MM			60.83		78.96		83.04		83.04
AC-FT			228.		295.		311.		311.
THOUS CU M			281.		364.		383.		383.

HYDROGRAPH AT STA000001 FOR PLAN 1. RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1697.	689.	723.	118.	33840.
CMS	48.	19.	6.	3.	958.
INCHES		3.59	4.66	4.90	4.90
MM		91.25	118.44	124.57	124.57
AC-FT		341.	443.	466.	466.
THOUS CU M		421.	547.	575.	575.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2262.	918.	298.	157.	45120.
CMS	64.	26.	8.	4.	1278.
INCHES		4.79	6.22	6.54	6.54
MM		121.67	157.92	166.09	166.09
AC-FT		455.	591.	621.	621.
THOUS CU M		562.	729.	767.	767.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3959.	1607.	521.	274.	78960.
CMS	112.	45.	15.	8.	2236.
INCHES		8.38	10.88	11.44	11.44
MM		212.91	276.37	290.66	290.66
AC-FT		797.	1034.	1088.	1088.
THOUS CU M		983.	1276.	1342.	1342.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 6 $\frac{1}{2}$ PM F

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	5656.	2295.	745.	392.	112800.
CMS	160.	65.	21.	11.	3194.
INCHES		11.97	15.54	16.35	16.35
MM		304.16	394.81	415.22	415.22
AC-FT		1138.	1477.	1554.	1554.
THOUS CU M		1404.	1822.	1916.	1916.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	8484.	3443.	1117.	588.	169201.
CMS	240.	97.	32.	17.	4791.
INCHES		17.96	23.32	24.52	24.52
MM		456.24	592.21	622.84	622.84
AC-FT		1707.	2216.	2331.	2331.
THOUS CU M		2106.	2733.	2875.	2875.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 8 PM F

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	11512.	4591.	1490.	783.	225601.

CMS 320. 130. 42. 22. 6388.
 INCHES 23.95 31.09 32.69 32.69
 MM 608.33 789.61 830.45 830.45
 AC-FI 2276. 2955. 3107. 3107.
 THOUS CU M 2808. 3645. 3833. 3833.

HYDROGRAPH ROUTING

ROUTED FLOWS THRU RESERVOIR 10261

ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
 000002 1 0 0 2 0 0 0

ROUTING DATA

QLOSS CLOSS AVG IRES ISAME IOPT IPMP LSTR
 0.0 0.000 0.00 1 1 0 0

NSTPS NSTOL LAG AMSKK X TSK STORA ISPRAT
 1 0 0 0.000 0.000 0.000 -110. -1

STAGE 110.00 110.50 111.00 111.50 112.00 113.00 113.50 114.00 115.00 116.00

FLOW 0.00 100.00 250.00 500.00 800.00 1550.00 2050.00 2580.00 4010.00 5550.00

SURFACE AREA= 0. 3. 16. 39. 73. 98. 130. 171.

CAPACITY= 0. 5. 91. 358. 909. 1335. 1903. 2653.

ELEVATION= 75. 80. 90. 100. 110. 115. 120. 125.

CREL SPWID COQW EXPW ELEV COQL CAREA EXPL
 110.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAM DATA


TOPEL COQD EXPD DAMHID
 113.7 2.8 1.5 1200.

CREST LENGTH 0. 44. 200. 325. 675. 825. 1015. 1100. 1200. 1300.

AT OR BELOW ELEVATION 113.7 113.9 114.2 114.4 115.0 115.0 115.1 115.2 115.5 116.3

STATION 000002 PLAN 1:1 RATIO 1

END OF PERIOD HYDROGRAPH ORIGINATES



•OVN•

STATION 000002, PLAN 1, RATIO 6 $\frac{1}{2}$ PMF

END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW									
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
1.	1.	2.	2.	2.	2.	2.	3.	3.	1.
4.	4.	5.	5.	5.	6.	7.	8.	10.	11.
13.	14.	16.	18.	21.	23.	25.	28.	31.	33.
36.	39.	42.	47.	53.	62.	72.	82.	91.	97.
101.	106.	110.	112.	114.	115.	116.	116.	116.	116.
114.	112.	109.	105.	101.	98.	95.	92.	83.	86.
84.	81.	78.	76.	73.	71.	69.	67.	65.	63.
61.	59.	57.	55.	53.	52.	50.	49.	47.	46.
45.	43.	42.	41.	40.	39.	38.	38.	38.	39.
40.	41.	42.	43.	45.	46.	47.	48.	49.	50.
51.	52.	53.	54.	55.	56.	57.	58.	59.	59.
60.	60.	61.	62.	62.	63.	63.	64.	65.	65.
66.	67.	70.	76.	83.	92.	102.	117.	132.	146.
161.	174.	187.	200.	211.	223.	233.	244.	255.	270.
284.	296.	308.	318.	328.	337.	345.	352.	358.	365.
371.	376.	381.	386.	390.	394.	398.	408.	427.	460.
505.	567.	632.	698.	765.	840.	922.	1000.	1073.	1144.
1214.	1286.	1359.	1431.	1499.	1567.	1637.	1708.	2053.	2462.
3103.	3756.	4082.	4031.	3781.	3493.	3227.	2996.	2796.	2618.
2489.	2376.	2269.	2159.	2032.	1888.	1724.	1551.	1421.	1294.
1174.	1062.	959.	865.	784.	722.	666.	614.	567.	524.
487.	457.	430.	404.	381.	360.	340.	322.	305.	290.
276.	264.	252.	245.	238.	233.	227.	222.		

STORAGE									
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
910.	910.	910.	910.	910.	910.	910.	910.	910.	910.
911.	911.	911.	911.	911.	911.	912.	913.	913.	913.
914.	915.	915.	916.	917.	918.	918.	919.	920.	921.
923.	925.	926.	926.	929.	933.	936.	940.	943.	945.
947.	948.	949.	949.	950.	950.	950.	950.	950.	950.
950.	949.	948.	948.	947.	945.	944.	943.	942.	941.
940.	939.	938.	937.	936.	935.	934.	933.	932.	932.
932.	931.	930.	930.	929.	928.	928.	927.	926.	926.
926.	925.	925.	924.	924.	923.	923.	923.	924.	924.
924.	925.	925.	925.	926.	926.	926.	927.	927.	928.
928.	928.	929.	929.	929.	930.	930.	930.	931.	931.
931.	931.	932.	932.	932.	933.	933.	933.	933.	933.
933.	934.	935.	937.	940.	943.	947.	951.	954.	958.
962.	965.	968.	972.	975.	978.	983.	985.	988.	988.
990.	992.	994.	995.	997.	998.	999.	1001.	1002.	1003.
1004.	1004.	1005.	1006.	1006.	1007.	1008.	1009.	1012.	1018.
1025.	1033.	1042.	1051.	1060.	1069.	1078.	1087.	1095.	1103.
1111.	1119.	1128.	1136.	1144.	1151.	1159.	1172.	1195.	1229.

◆OVF◆

STATION000002

	0.	1000.	2000.	3000.	4000.	5000.	6000.	0.	0.	0.	0.	0.	0.	0.	0.
10 11
20 21
30 31
40 41
50 51
1.00 61
1.10 71
1.20 81
1.30 91
1.40 101
1.50 111
2.00 121
2.10 131
2.20 141
2.30 151
2.40 161
2.50 171
3.00 181
3.10 191
3.20 201
3.30 211
3.40 221
3.50 231
4.00 241
4.10 251
4.20 261
4.30 271
4.40 281
4.50 291
5.00 301
5.10 311
5.20 321
5.30 331
5.40 341
5.50 351
6.00 361
6.10 371
6.20 381
6.30 391
6.40 401
6.50 411
7.00 421
7.10 431
7.20 441
7.30 451
7.40 461
7.50 471
8.00 481
8.10 491
8.20 501
8.30 511
8.40 521
8.50 531
9.00 541
9.10 551
9.20 561

9.30 571
9.40 581
9.50 591
10.00 601
10.10 611
10.20 621
10.30 631
10.40 641
10.50 651
11.00 661
11.10 671
11.20 681
11.30 691
11.40 701
11.50 711
12.00 721
12.10 731
12.20 741
12.30 751
12.40 761
12.50 771
13.00 781
13.10 791
13.20 801
13.30 811
13.40 821
13.50 831
14.00 841
14.10 851
14.20 861
14.30 871
14.40 881
14.50 891
15.00 901
15.10 911
15.20 921
15.30 931
15.40 941
15.50 951
16.00 961
16.10 971
16.20 981
16.30 991
16.40 1001
16.50 1011
17.00 1021
17.10 1031
17.20 1041
17.30 1051
17.40 1061
17.50 1071
18.00 1081
18.10 1091
18.20 1101
18.30 1111
18.40 1121
18.50 1131
19.00 1141
19.10 1151
19.20 1161
19.30 1171
19.40 1181

6.10181.1
6.20182.1
6.30183.01
6.40184.01
6.50185.0
7.00186.0
7.10187.0
7.20188.0
7.30189.0
7.40190.0
7.50191.0
8.00192.0
8.10193.0
8.20194.0
8.30195.0
8.40196.0
8.50197.0
9.00198.0
9.10199.0
9.20200.0
9.30201.0
9.40202.0
9.50203.0
10.00204.0
10.10205.0
10.20206.0
10.30207.0
10.40208.0
10.50209.0
11.00210.0
11.10211.0
11.20212.0
11.30213.0
11.40214.0
11.50215.0
12.00216.0
12.10217.0
12.20218.0
12.30219.0
12.40220.0
12.50221.0
13.00222.0
13.10223.0
13.20224.0
13.30225.0
13.40226.0
13.50227.0
14.00228.0
14.10229.0
14.20230.0
14.30231.0
14.40232.0
14.50233.0
15.00234.0
15.10235.0
15.20236.0
15.30237.0
15.40238.0
15.50239.0
16.00240.0
16.10241.0
16.20242.0

PLATE D-19

•UVN•

STATION 000002, PLAN 1, RATIO 8 PMF

END-OF-PERIOD HYDROGRAPH ORIGINATES

OUTFLOW														
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
2.	3.	3.	4.	4.	4.	4.	4.	4.	4.	4.	4.	4.	4.	4.
7.	8.	8.	9.	9.	9.	9.	9.	9.	9.	9.	9.	9.	9.	9.
25.	29.	33.	37.	41.	46.	50.	55.	61.	66.	72.	77.	83.	88.	94.
72.	78.	84.	92.	107.	134.	164.	192.	214.	230.	254.	282.	316.	358.	397.
241.	254.	259.	263.	262.	261.	262.	261.	262.	261.	262.	261.	262.	261.	262.
249.	243.	236.	228.	219.	210.	201.	192.	183.	174.	166.	159.	151.	144.	137.
166.	159.	151.	144.	137.	131.	125.	119.	114.	109.	104.	100.	97.	94.	91.
77.	75.	72.	70.	69.	67.	66.	64.	62.	60.	58.	56.	54.	52.	50.
72.	74.	77.	79.	82.	84.	87.	89.	92.	94.	96.	98.	101.	104.	106.
121.	123.	124.	126.	128.	129.	131.	132.	134.	135.	137.	139.	141.	143.	145.
137.	141.	150.	164.	185.	209.	236.	272.	316.	358.	397.	434.	468.	500.	534.
683.	701.	716.	731.	744.	755.	766.	776.	784.	792.	800.	808.	815.	821.	827.
1112.	1245.	1384.	1524.	1699.	1879.	2051.	2221.	2377.	2530.	2720.	2940.	3168.	3390.	3588.
9833.	10503.	9846.	8565.	7324.	6381.	5695.	5196.	4814.	4484.	4198.	3959.	3755.	3544.	3281.
1712.	1528.	1395.	1272.	1160.	1058.	966.	884.	810.	755.	707.	663.	623.	587.	556.
426.	411.	398.	385.	374.	364.	354.	346.	336.	326.	316.	306.	296.	286.	276.

STORAGE

909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.	909.
910.	910.	910.	911.	911.	911.	911.	911.	911.	911.	911.	911.	911.	911.	911.
912.	912.	912.	913.	913.	913.	913.	913.	913.	913.	913.	913.	913.	913.	913.
918.	920.	921.	923.	924.	926.	928.	930.	932.	934.	936.	938.	940.	942.	944.
936.	938.	940.	943.	948.	955.	962.	970.	975.	982.	986.	988.	990.	992.	994.
984.	983.	981.	979.	977.	974.	972.	970.	967.	965.	963.	961.	959.	957.	955.
963.	961.	959.	957.	956.	954.	953.	951.	950.	949.	948.	947.	946.	945.	944.
947.	946.	945.	944.	943.	942.	941.	940.	939.	938.	937.	936.	935.	934.	933.
936.	937.	938.	935.	935.	934.	934.	934.	934.	934.	934.	934.	934.	934.	934.
945.	946.	946.	947.	948.	949.	950.	950.	950.	950.	950.	950.	950.	950.	950.
956.	957.	959.	963.	968.	974.	981.	988.	995.	1001.	1008.	1013.	1019.	1024.	1029.
1008.	1013.	1019.	1024.	1029.	1033.	1037.	1040.	1043.	1046.	1049.	1051.	1053.	1055.	1057.
1065.	1066.	1066.	1067.	1068.	1068.	1069.	1071.	1073.	1075.	1077.	1079.	1081.	1083.	1085.
1099.	1115.	1130.	1147.	1163.	1179.	1194.	1209.	1222.	1235.	1247.	1259.	1270.	1280.	1288.
1247.	1259.	1270.	1280.	1288.	1295.	1302.	1317.	1347.	1387.					

1418.	1427.	1418.	1400.	1380.	1364.	1350.	1330.	1329.	1319.
1310.	1302.	1294.	1286.	1275.	1260.	1242.	1223.	1202.	1182.
1164.	1117.	1132.	1118.	1105.	1093.	1083.	1074.	1066.	1059.
1052.	1046.	1041.	1036.	1031.	1027.	1024.	1020.	1017.	1015.
1012.	1010.	1008.	1006.	1004.	1002.	1001.	1000.		

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	10503.	4373.	1457.	761.	219038.
CMS	297.	124.	41.	22.	6202.
INCHES		22.82	30.41	31.74	
MM		579.55	772.42	806.29	
AC-FT		2169.	2890.	3017.	
HOUS CU M		2675.	3565.	3721.	

STAT1UN000002

[illegible]

9.30 571
9.40 581
9.50 591
10.00 601
10.10 611
10.20 621
10.30 631
10.40 641
10.50 651
11.00 661
11.10 671
11.20 681
11.30 691
11.40 701
11.50 711
12.00 721
12.10 731
12.20 741
12.30 751
12.40 761
12.50 771
13.00 781
13.10 791
13.20 801
13.30 810
13.40 820
13.50 830
14.00 840
14.10 850
14.20 860
14.30 870
14.40 880
14.50 890
15.00 900
15.10 910
15.20 920
15.30 930
15.40 940
15.50 950
16.00 960
16.10 970
16.20 980
16.30 990
16.40 1000
16.50 1010
17.00 1020
17.10 1030
17.20 1040
17.30 1050
17.40 1060
17.50 1070
18.00 1080
18.10 1090
18.20 1100
18.30 1110
18.40 1120
18.50 1130
19.00 1140
19.10 1150
19.20 1160
19.30 1170
19.40 1180

19.5011910
20.0012010
20.1012110
20.2012210
20.3012310
20.4012410
20.5012510
21.0012610
21.1012710
21.2012810
21.3012910
21.4013010
21.5013110
22.001321
22.101331
22.201341
22.301351
22.401361
22.501371
23.001381
23.101391
23.201401
23.301411
23.401421
23.501431
0.001441
101451
201461
301471
401481
5014901
1.0015001
1.1015101
1.2015201
1.3015301
1.4015401
1.5015501
2.0015601
2.1015701
2.2015801
2.3015901
2.4016001
2.5016101
3.0016201
3.101631
3.201641
3.301651
3.401661
3.501671
4.001681
4.101691
4.201701
4.301711
4.401721
4.501731
5.001741
5.101751
5.201761
5.301771
5.401781
5.501791
6.001801

PEAK FLOW AND STORAGE TEND OF PERIODI SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO	RATIOS APPLIED TO FLOWS							
					1	2	3	4	5	6	7	8
					.05	.10	.15	.20	.35	.50	.75	1.00
HYDROGRAPH AT	000001	1.78	1	566.	1131.	1697.	2262.	3959.	5656.	8484.	11312.	
	(4.62)	(16.02)	(32.03)	(48.05)	(64.07)	(112.12)	(160.17)	(240.25)	(320.33)	
ROUTED TO	000002	1.78	1	219.	543.	895.	1258.	2418.	4082.	7418.	10503.	
	(4.62)	(6.20)	(15.36)	(25.36)	(35.61)	(68.46)	(115.58)	(210.07)	(297.42)	

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION STORAGE	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
OUTFLOW	110.00	110.00	113.70
	909.	909.	1212.
	0.	0.	2262.

RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.05	110.90	0.00	977.	219.	0.00	41.33	0.00
.10	111.57	0.00	1030.	543.	0.00	41.00	0.00
.15	112.13	0.00	1075.	895.	0.00	40.83	0.00
.20	112.61	0.00	1116.	1258.	0.00	40.83	0.00
.35	113.84	.14	1226.	2418.	.67	40.67	0.00
.50	114.70	1.00	1306.	4082.	2.33	40.50	0.00
.75	115.47	1.77	1382.	7418.	3.83	40.33	0.00
1.00	115.91	2.21	1427.	10503.	5.00	40.33	0.00